
# 1410 RD CLEARANCES

#### TIMBER FRAME



#### **CLEARANCE TO COMBUSTIBLES**

Uni	t Dimens	ons	Timber Frame			Metal Studs Infills to be installed after Unit is in place (Clearance between unit and metal stud infill)	
	In mm		Clearance to Combustibles in mm			Installation dimensions in mm	
			Unit Height +500mmtop	UnitWidth +250mm each side	UnitDepth +250mm to back	Unit Width +50mm either side	Unit Height +150mm top
Н	W	D	А	В	С	D	E
850	1500	420	1350	2000	N/A	1600	1000


### Extra notes:

- Fortimberframeinstallations the unit can be either floor mounted or mid mounted. However, for steel frame installations, the appliance must be mid mounted.
- Drawings above are for visual illustration purposes only. When the appliance is symmetrical you may choose to change the location of the control box or vents given you meet the minimum clearance requirements.
- For installations where the control box is below the appliance to the side of the cavity, you may choose to install the vent below the control box (not shown in the drawings) given the appliance is raised high enough to allow the minimum clearances and there is a dequate space for the vent.
- The external façade/surrounding of the timber/steel frame should be constructed with 9mm Villa board (minimum).
- ${\tt *Gdimension} is only applicable if the control box is installed to the side of the cavity, in line or above from the bottom of the appliance. Similarly, H dimension is only applicable if the control box is installed either directly below the appliance or below the appliance to the side of the cavity dimension is only applicable if the control box is installed either directly below the appliance or below the appliance to the side of the cavity dimension is only applicable. \\$

28.

# 1410 RD CLEARANCES

### METAL FRAME



## **CLEARANCE TO COMBUSTIBLES**

Unit Dimensions			Metal Stud Frame				
			FOR METAL STUD FRAME, UNIT MUST BE IN PLACE				
In mm		Clearance to the inside of the metal stud					
		Unit Height +50mm top	Unit Width +150mm either side to internal side of metal stud	Reduced Depth Clearance N/A for Tunnel Units Metal Studs fixed to rear combustible wall. 25mm Steel Battens fixed to combustible wall +13mm Firestop Board +50mm air gap to unit			
Н	W	D	Α	В	С		
850	1500	420	900	1800	N/A		

### Extra notes:

- Fortimberframeinstallations the unit can be either floor mounted or mid mounted. However, for steel frame installations, the appliance must be mid mounted.
- Drawings above are for visual illustration purposes only. When the appliance is symmetrical you may choose to change the location of the control box or vents given you meet the minimum clearance requirements.
- For installations where the control box is below the appliance to the side of the cavity, you may choose to install the vent below the control box (not shown in the drawings) given the appliance is raised high enough to allow the minimum clearances and there is a dequate space for the vent.
- The external façade/surrounding of the timber/steel frame should be constructed with 9mm Villa board (minimum).
- ${\tt *Gdimension} is only applicable if the control box is installed to the side of the cavity, in line or above from the bottom of the appliance. Similarly, H dimension is only applicable if the control box is installed either directly below the appliance or below the appliance to the side of the cavity and the cavity below the appliance of the cavity below. \\$